

PS-15-2

- 15.1.6 The Contractor shall transport all rock and/or soil samples from site investigation undertaken by the Authority's site investigation contractors and store in sheltered storage until Completion of the whole of the Works. The rock and/or soil samples shall be stored using new storage racks and trays such that the samples are readily available for inspection. The Contractor shall store all rock and/or soil samples from his site investigation at the same location. Upon Completion of the whole of the Works, the Contractor shall dispose of the rock and/or soil samples or transport to such location specified by the Engineer.
- 15.1.7 Where additional soil investigation is carried out by, or on behalf of, the Contractor, he shall first seek the acceptance of the Engineer before commencing any investigation works. A duplicate copy of the report shall be provided to the Engineer in both hard and soft copy within one (1) month from the completion date of the investigation works. The soft copy of the soil investigation report shall be in 'Association of Geotechnical and Geo-environment Specialist' (AGS) and in Excel or equivalent format. The PDF format shall be created by converting from the original digital format, such as doc, xls, dwg, dgn, etc., instead of by scanning printouts unless allowed by the Engineer.
- 15.1.8 The Contractor shall comply with the implementation of accreditation requirements for site investigation works under Regulation 31(2) of the Building Control Regulations. The Contractor shall take note that the implemented regulations require the Qualified Person (QP) to ensure that all site investigation works are carried out by an accredited inspection body approved by the Singapore Accreditation Council (SAC) under the Council's scheme for Accreditation of Inspection Bodies for Site Investigation.
- 15.1.9 The Contractor shall provide secured shelter storage within the Engineer's Office which is accessible by authorized personnel and transport all rock and/or soil samples from site investigation undertaken by the Authority's site investigation contractors and store in sheltered storage until Completion of the whole of the Works. The rock and/or soil samples shall be stored using new storage racks and trays such that the samples are readily available for inspection. The Contractor shall store all rock and/or soil samples from his site investigation at the same location. Upon Completion of the whole of the Works, the Contractor shall dispose of the rock and/or soil samples or transport to such location specified by the Engineer.